



01 CONCRETE PATH - SECTION
SCALE: 1:20 @ A4




02 HEAVY DUTY CONCRETE PATH - SECTION
SCALE: 1:20 @ A4



03 NO DIG CONCRETE PATH WITHIN TREE PROTECTION ZONE

QUICK SPECIFICATION

APPLICATION OR TYPICAL LOCATION:	FOOTPATHS IN PARKS AND PUBLIC SPACE, AS DIRECTED BY THE COUNCIL REPRESENTATIVE.
PRODUCT:	CONTRACTOR TO NOMINATE
SUPPLIER:	CONTRACTOR TO NOMINATE
MATERIAL AND FINISH:	STANDARD GREY CEMENT, BROOM FINISH, 10mm RADIUS TOOLED EDGE WITH NO HIGHLIGHT. SAWCUTS AT 1:1 RATIO - 1500mm CENTRES FOR 1500mm WIDE PATH - 2500mm CENTRES FOR 2500mm WIDE PATH EXPANSION JOINTS AT 1:4 RATIO - 6000mm CENTRES FOR 1500mm WIDE PATH - 10000mm CENTRES FOR 2500mm WIDE PATH THE CONTRACTOR SHALL INSTALL EXPANSION AND SAW-CUT JOINTS WITHIN 24 HOURS OF POURING. FINISH JOINT-FILLER FOR THE EXPANSION JOINTS (IF APPLICABLE) SHALL BE APPLIED NEATLY AND FLUSH WITH ADJACENT SURFACES. SAW CUT JOINTS SHOULD BE SPACED AT INTERVALS TO MATCH THE PATH WIDTH.
FIXING / FOOTING:	NOT APPLICABLE
ADDITIONAL OPTIONS:	NOT APPLICABLE
AUSTRALIAN STANDARDS:	AS 3972 GENERAL PURPOSE AND BLENDED CEMENTS; AS 2758.1 AGGREGATES AND ROCK FOR ENGINEERING PURPOSES CONCRETE AGGREGATES; AS 1478 CHEMICAL ADMIXTURES FOR CONCRETE; AS 1379 SPECIFICATION AND SUPPLY OF CONCRETE; AS 3600 CONCRETE STRUCTURES; AS 3610 FRAMEWORK FOR CONCRETE.
STANDARD DRAWING CROSS REFERENCES:	EDCM - ENGINEERING DESIGN AND CONSTRUCTION MANUAL



Drawn	HK
Checked	AC, AN
Approved	JG
Date	JUNE 2023



STANDARD DETAIL
LANDSCAPE CONSTRUCTION DETAIL
CONCRETE PATH DETAIL

DWG NO.
SDL.3.01

REVISION_A